

NOTICE TO CONTRACTORS
PROJECT NO. JCP-51-15-03
JEFFERSON COUNTY, ALABAMA

Sealed bids marked “**Widening Brooklane Dr**” will be received by the Commission of Jefferson County, Alabama, Jefferson County Commission Chambers, Room 270, Jefferson County Courthouse, Birmingham, Alabama, until 10:00 a.m. on December 10, 2015. No bids will be received after the time set forth hereinafter, and the proposals will be publicly opened and read aloud. Name of contractor, contractor’s address and license number must be on proposal envelope.

The work to be performed under this contract consists of grading, drainage, paving, and signal modification of the following roadway:

Widening Brooklane Drive from Opal Avenue to Allison Bonnett Memorial Drive

Alabama Department of Transportation Standard Specifications for Highway Construction, 2012 Edition and Special Provisions will be used for the project.

The entire project shall be completed in **220 working days**.

Proposal fee is \$30.00. Plans are available for \$60.00. Plans and Proposals are available in the Office of the Director/County Engineer, 716 Richard Arrington Jr. Boulevard North, A200, Birmingham, Alabama. A full refund will be issued to each general contract bidder submitting a bonafide bid, upon return of documents in good condition within ten days of bid date.

The Jefferson County Commission encourages the voluntary utilization of qualified resident Jefferson County contractors, minority contractors, and disadvantaged contractors who live, work, and do business in Jefferson County.

The minimum paid to all skilled intermediate and unskilled labor employed on this Contract shall be as set forth in the Special Provisions.

A Certified check or bid bond for 5 percent of total bid, made payable to the Commission of Jefferson County must accompany each bid as evidence of good faith. The maximum per contract is \$50,000 per contract for bids \$1,000,000 or more. The Bid Bond shall be forfeited to Jefferson County, Alabama, as liquidated damages if the BIDDER fails to execute the Contract and provide Performance and Payment Bonds within ten (10) days after being notified that he had been awarded the Contract.

The items of work under this Contract are as follows:

PROJECT NO. JCP-51-15-03, Widening Brooklane Drive from Opal Avenue to Allison Bonnett Memorial Drive

All quantities are approximate and may vary as needed.

<u>Quantity</u>	<u>Unit</u>	<u>Description</u>
1	LUMP SUM	CLEARING AND GRUBBING (MAXIMUM ALLOWABLE BID \$4000.00 PER ACRE) (APPROXIMATELY 9 ACRES)
1	EACH	REMOVAL OF OLD BRIDGE, STATION 61+32
507	SQ YD	REMOVING CONCRETE DRIVEWAY
3533	LIN FT	REMOVING PIPE
207	LIN FT	REMOVING CURB
875	LIN FT	REMOVING CURB AND GUTTER
81	LIN FT	REMOVING GUTTER
7	EACH	REMOVING HEADWALLS
4	EACH	REMOVING INLETS
8153	CU YD	UNCLASSIFIED EXCAVATION
18554	CU YD	BORROW EXCAVATION
3895	CU YD	STRUCTURE EXCAVATION
1518	CU YD	FOUNDATION BACKFILL, COMMERCIAL
60	ROADBED STATION	ROADBED PROCESSING
8	CU YD	CEMENT MORTAR FLOWABLE BACKFILL, MIX 1
44771	SQ YD	CRUSHED AGGREGATE BASE COURSE, TYPE B, PLANT MIXED, 6" COMPACTED THICKNESS
96	TON	COARSE AGGREGATE, SECTION 801, FOR MISCELLANEOUS USE
44088	SQ YD	BITUMINOUS TREATMENT A
3339	GALLON	TACK COAT
5	MILE	JOINT SEALANT FOR HOT MIX ASPHALT PAVEMENT
8195	SQ YD	PLANING EXISTING PAVEMENT (APPROXIMATELY 1.10" THRU 2.0" THICK)
4309	TON	SUPERPAVE BITUMINOUS CONCRETE WEARING SURFACE LAYER, 1/2" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D
5459	TON	SUPERPAVE BITUMINOUS CONCRETE UPPER BINDER LAYER, 1" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D
156	TON	SUPERPAVE BITUMINOUS CONCRETE UPPER BINDER LAYER, PATCHING, 3/4 " MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D
1020	TON	SUPERPAVE BITUMINOUS CONCRETE UPPER BINDER LAYER, LEVELING, 3/4" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D
7645	TON	SUPERPAVE BITUMINOUS CONCRETE BASE LAYER, 1" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE C/D
1770	TON	AGGREGATE SURFACING (1" DOWN, CRUSHER RUN)
20243	LB	STEEL REINFORCEMENT

108	CU YD	CULVERT CONCRETE
861	LIN FT	18" ROADWAY PIPE (CLASS 3 R.C.)
65	LIN FT	24" ROADWAY PIPE (CLASS 3 R.C.)
48	LIN FT	12" ROADWAY PIPE (CLASS 3 R.C.)
130	LIN FT	29" SPAN 18" RISE ROADWAY PIPE (CLASS 3 R.C.)
65	LIN FT	36" SPAN 23" RISE ROADWAY PIPE (CLASS 3 R.C.)
956	LIN FT	18" STORM SEWER PIPE (CLASS 3 R.C.)
1577	LIN FT	24" STORM SEWER PIPE (CLASS 3 R.C.)
793	LIN FT	30" STORM SEWER PIPE (CLASS 3 R.C.)
157	LIN FT	18" STORM SEWER PIPE (CLASS 3 R.C.)(EXTENSION)
115	LIN FT	12" STORM SEWER PIPE
107	LIN FT	29" SPAN 18" RISE STORM SEWER PIPE (CLASS 3 R.C.)
26	LIN FT	36" SPAN, 23" RISE STORM SEWER PIPE (CLASS 3 R.C.)
125	LIN FT	18" SIDE DRAIN PIPE
25	LIN FT	22" SPAN, 14" RISE SIDE DRAIN PIPE
1	LUMP SUM	MOBILIZATION
720	SQ YD	FILTER BLANKET, GEOTEXTILE
18	CU YD	SLOPE PAVING
405	SQ YD	CONCRETE DRIVEWAY, 6" THICK (INCLUDES WIRE MESH)
2	EACH	12" ROADWAY PIPE END TREATMENT, CLASS 1
4	EACH	18" ROADWAY PIPE END TREATMENT, CLASS 1
5	EACH	24" ROADWAY PIPE END TREATMENT, CLASS 2
1	EACH	30" ROADWAY PIPE END TREATMENT, CLASS 2
6	EACH	18" SIDE DRAIN PIPE END TREATMENT, CLASS 1
2	EACH	29" SPAN, 18" RISE ROADWAY PIPE END TREATMENT, CLASS 1
2	EACH	36" SPAN, 23" RISE ROADWAY PIPE END TREATMENT, CLASS 2
2	EACH	22" SPAN, 14" RISE SIDE DRAIN PIPE END TREATMENT, CLASS 1
10	CU YD	MINOR STRUCTURE CONCRETE
14	EACH	JUNCTION BOXES, TYPE 1 OR 1P
1	EACH	INLETS, TYPE C, P1 OR P3
1	EACH	INLETS, TYPE E
30	EACH	INLETS, TYPE S1 OR S3 (1 WING)
3	EACH	INLETS, TYPE S1 OR S3 (2 WING)
20	EACH	INLETS, TYPE S3 (1 WING)
2	EACH	INLETS, TYPE S3 (2 WING)
2	EACH	INLETS, TYPE PD
2	EACH	INLET UNITS, TYPE E
12	EACH	INLET UNITS, TYPE S1 OR S3
17	EACH	INLET UNITS, TYPE S3
1	EACH	INLET UNITS, TYPE C, P1 OR P3
4	LIN FT	MANHOLE HEIGHT ADJUSTMENT
5	EACH	MANHOLE COVERS RESET
2238	LIN FT	CONCRETE GUTTER (4'0" WIDE)

22	LIN FT	CONCRETE CURB, TYPE A
9685	LIN FT	COMBINATION CURB & GUTTER, TYPE C
2675	CU YD	TOPSOIL
4	ACRE	SEEDING
4	ACRE	MOWING
5109	SQ YD	SOLID SODDING (BERMUDA)
4	ACRE	MULCHING
524	SQ YD	EROSION CONTROL PRODUCT, TYPE S2
4	ACRE	TEMPORARY SEEDING
12	TON	TEMPORARY MULCHING
120	EACH	HAY BALES
370	EACH	SAND BAGS
20	TON	TEMPORARY RIPRAP, CLASS 2
14097	LIN FT	SILT FENCE
660	TON	TEMPORARY COARSE AGGREGATE, ALDOT NUMBER 1
4	TON	TEMPORARY COARSE AGGREGATE, ALDOT NUMBER 4
14097	LIN FT	SILT FENCE REMOVAL
73	EACH	INLET PROTECTION, STAGE 3 OR 4
4850	LIN FT	WATTLE
4	ACRE	PEST CONTROL TREATMENT
500	LIN FT	CONSTRUCTION SAFETY FENCE
1	MILE	SOLID WHITE, CLASS 2, TYPE A TRAFFIC STRIPE (5" WIDE)
3	MILE	SOLID YELLOW, CLASS 2, TYPE A TRAFFIC STRIPE (5" WIDE)
2	MILE	BROKEN WHITE, CLASS 2, TYPE A TRAFFIC STRIPE (5" WIDE)
2	MILE	BROKEN YELLOW, CLASS 2, TYPE A TRAFFIC STRIPE (5" WIDE)
606	LIN FT	DOTTED, CLASS 2, TYPE A TRAFFIC STRIPE (LANE DROP 10" WIDE)
800	LIN FT	DOTTED, CLASS 2, TYPE A TRAFFIC STRIPE (5" WIDE)
4	MILE	BROKEN TEMPORARY TRAFFIC STRIPE
4	MILE	SOLID TEMPORARY TRAFFIC STRIPE
128	LIN FT	DOTTED TEMPORARY TRAFFIC STRIPE
3949	SQ FT	TRAFFIC CONTROL MARKINGS, CLASS 2, TYPE A
696	SQ FT	TRAFFIC CONTROL LEGENDS, CLASS 2, TYPE A
938	SQ FT	TEMPORARY TRAFFIC CONTROL MARKINGS
38	EACH	PAVEMENT MARKERS, CLASS B, TYPE 1-A
135	EACH	PAVEMENT MARKERS, CLASS B, TYPE 1-B
373	EACH	PAVEMENT MARKERS, CLASS C, TYPE 1-A
371	EACH	PAVEMENT MARKERS, CLASS C, TYPE 2-D
129	EACH	PAVEMENT MARKERS, CLASS A-H, TYPE 2-C
84	EACH	PAVEMENT MARKERS, CLASS A-H, TYPE 1-A
277	EACH	PAVEMENT MARKERS, CLASS A-H, TYPE 1-B
177	EACH	PAVEMENT MARKERS, CLASS A-H, TYPE 2-D
140	EACH	PAVEMENT MARKERS, CLASS A-H, TYPE 2-E

60	SQ FT	CLASS 4, ALUMINUM FLAT SIGN PANELS 0.08" THICK OR STEEL FLAT SIGN PANELS 14 GAUGE (TYPE III OR IV BACKGROUND)
4	SQ FT	CLASS 8, ALUMINUM FLAT SIGN PANELS 0.08" THICK OR STEEL FLAT SIGN PANELS 14 GAUGE (TYPE IX BACKGROUND)
140	LIN FT	ROADWAY SIGN POST (#3 U CHANNEL GALVANIZED STEEL OR 2", 14 GA SQUARE TUBULAR STEEL)
1	LUMP SUM	ROADWAY SIGN RELOCATION
2640	LIN FT	PORTABLE CONCRETE SAFETY BARRIERS, TYPE 6
160	LIN FT	PORTABLE CONCRETE SAFETY BARRIERS, TYPE 6-A
16	EACH	PORTABLE IMPACT ATTENUATOR ASSEMBLY (UNIDIRECTIONAL, TL-3)
1	LUMP SUM	REMOVAL OF EXISTING TRAFFIC CONTROL UNIT (PARTIAL)(ALLISON BONNET MEMORIAL DR AT BROOKLANE DR)
1	LUMP SUM	FURNISHING AND INSTALLING TRAFFIC CONTROL UNIT (ALLISON BONNET MEMORIAL DR AND BROOKLANE DR)
1	EACH	METAL TRAFFIC SIGNAL POLE FOUNDATION
1	EACH	METAL TRAFFIC SIGNAL STRAIN POLE
3920	LIN FT	LOOP WIRE
200	LIN FT	LOOP DETECTOR LEAD-IN-CABLE
1	EACH	TRAFFIC SIGNAL JUNCTION BOX
50	LIN FT	1", NON-METALLIC, CONDUIT
100	LIN FT	2", NON-METALLIC, CONDUIT
1	EACH	LUMINAIRE EXTENSION ASSEMBLY, 15 FEET
9	EACH	VEHICULAR SIGNAL HEAD, 12 INCH, 3 SECTION, TYPE LED
1	EACH	VEHICULAR SIGNAL HEAD, 12 INCH, 4 SECTION, TYPE LED
1	EACH	VEHICULAR SIGNAL HEAD, 12 INCH, 5 SECTION, TYPE LED
723	SQ FT	CONSTRUCTION SIGNS
700	EACH	CHANNELIZING DRUMS
100	EACH	CONES (36 INCHES HIGH)
116	EACH	BARRICADES, TYPE III
58	EACH	WARNING LIGHTS, TYPE B
100	EACH	BALLAST FOR CONE
2	EACH	PORTABLE SEQUENTIAL ARROW AND CHEVRON SIGN UNIT
2	EACH	PORTABLE CHANGEABLE MESSAGE SIGN, TYPE 2
160	HOUR	UNIFORMED POLICE OFFICER

Performance Bond and Labor and Payment Bond will be required of the successful BIDDER. Performance Bond must be in the penal amount of 100% of the Contract price and Payment Bond in the penal amount of 100% of the Contract price. Bonds must be executed by a Surety company acceptable to the Commission of Jefferson County, Alabama and authorized to do business in the State of Alabama.

The Contractor is hereby advised that time is of the essence on this project and that the contract time limit of Two Hundred Twenty (220) working days shall be strictly observed.

LIQUIDATED DAMAGES WILL BE ASSESSED IF THE CONTRACT TIME IS EXCEEDED. Liquidated damages shall be paid if necessary based on the Alabama Department of Transportation Standard Specifications for Highway Construction 2012 Edition, Section 108.11 Special Provision No. 12-0426(2). The Contractor may apply for an extension of time; however, such an extension of time must be approved PRIOR to the contract completion date to avoid imposition of liquidated damages.

The Contractor shall obtain and pay for all licenses and permits required by the State, County and City authorities having jurisdiction over the work.

Proposals will be issued only to pre-qualified contractors (must be on the ALDOT Pre-qualified Contractors List) or their authorized representatives upon request that are received before 1 p.m. on December 1, 2015. A pre-bid conference will be held on Tuesday, December 1, 2015 at 1:30 p.m. at the Jefferson County Department of Roads and Transportation Conference Room A200 Courthouse, Birmingham, Alabama for the purpose of clarifying any questions any potential bidder may have with regard to the plans and specifications.

THE ATTENTION OF ALL BIDDERS IS CALLED TO THE PROVISIONS OF THE STATE LAW GOVERNING GENERAL CONTRACTORS, AS SET FORTH IN ALABAMA CODE SECTIONS 34-8-1 THROUGH SECTION 34-8-28 (1975), AS AMENDED; AND BIDDERS SHALL BE GOVERNED BY SAID LAW INsofar AS IT IS APPLICABLE. THE ABOVE MENTIONED PROVISIONS OF THE CODE MAKE IT ILLEGAL FOR THE OWNER TO CONSIDER A BID PROPOSAL FROM ANYONE WHO IS NOT PROPERLY LICENSED UNDER SUCH CODE PROVISIONS.

THE ATTENTION OF BIDDERS IS CALLED TO THE PROVISIONS OF ALABAMA CODE SECTION 39-2-14 (1975) AS AMENDED, REQUIRING A NONRESIDENT CONTRACTOR TO REGISTER WITH THE DEPARTMENT OF REVENUE PRIOR TO ENGAGING IN THE PERFORMANCE OF A CONTRACT IN THE STATE OF ALABAMA.

THE ATTENTION OF BIDDERS IS CALLED TO THE PROVISIONS OF ALABAMA CODE SECTION 39-3-5 (1975) AS AMENDED, REGARDING PREFERENCE TO RESIDENT CONTRACTORS.

Jefferson County may make such investigations as deems necessary to determine the ability of the BIDDER to perform the WORK, and the BIDDER shall furnish to Jefferson County all such information and data for this purpose as Jefferson County may request. Jefferson County reserves the right to reject any BID if the evidence submitted by, or investigation of, such BIDDER fails to satisfy Jefferson County that such bidder is properly qualified to carry out the obligations of the Agreement and to complete the WORK contemplated therein.

The Commission of Jefferson County, Alabama hereby notifies all bidders Jefferson County is an equal opportunity employer in accordance with Title VII, Civil Rights Act of 1964, 42 U.S.C.

§§ 1981, 1983, 1986 and amendments, and it is the policy of Jefferson County to require contractors, vendors and suppliers (hereinafter "Contractor") providing goods and services to the County to afford equal opportunity for employment to all individuals regardless of race, color, sex, age, religion, national origin, disability or veteran status. (Please see Administrative Order of the Jefferson County Commission 08-4 for the complete disclosure).

Statement of Compliance with Alabama Code Section 31-13-9.

By signing this contract, the contracting parties affirm, for the duration of the agreement, that they will not violate federal immigration law or knowingly employ, hire for employment, or continue to employ unauthorized alien within the State of Alabama. Furthermore, a contracting party found to be in violation of this provision shall be deemed in breach of the agreement and shall be responsible for all damages resulting therefrom.

The Commission reserves the right to reject any and all bid proposals and to waive all informalities.